BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/OW/WORK_INDENT24255

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Earth work and other Works for Temporary tank for lord Ganesh Idols at Thindlu Vidyaranyapura Main Road near BWSSB overhead tank Ward No. 09 (Vidyaranyapura) Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R CHIDANANDA	
				In Figures	In Words
1	25.2	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications,	Cum	158.0	Rupees One Hundred Fifty Eight Only
2	187.5	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary Soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications,	Cum	190.0	Rupees One Hundred Ninety Only
3	187.5	Above 1.5 Mtrs Depth Add 25% Extra	Cum	238.0	Rupees Two Hundred Thirty Eight Only
4	820	Code 0516 - Providing Plastic Sheet	Sqm	5.7	Rupees Five and Seventy Paise Only
5	165	Supply of water Through water Tank for filling Tank	Each	342.0	Rupees Three Hundred Forty Two Only
6	12.5	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal Component	Cum	760.0	Rupees Seven Hundred Sixty Only
7	66	Hire charge of pumping water 3.5 KL/hr capacity Pump	Hr	48.0	Rupees Forty Eight Only
8	165	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the pooja Time	Days	246.0	Rupees Two Hundred Forty Six Only
9	480	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge.	M	62.0	Rupees Sixty Two Only
10	13200	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft)	Sft	7.6	Rupees Seven and Sixty Paise Only
11	165	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft)	Rft	16.0	Rupees Sixteen Only
12	220	Hire Charge for Armless Plastic Chairs	Nos	4.0	Rupees Four Only
13	110	Hire Charge for Wooden Table of Size 6ft x 2ft	Nos	38.0	Rupees Thirty Eight Only
14	1100	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire	M	3.8	Rupees Three and Eighty Paise Only
15	66	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges	Hr	600.0	Rupees Six Hundred Only
16	88	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time	Nos	271.0	Rupees Two Hundred Seventy One Only
17	10	Hire charges compoment name 1087 Crane charges	Days	3800.0	Rupees Three Thousand Eight Hundred Only
18	357.5	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour complete as per specifications,	Cum	78.0	Rupees Seventy Eight Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

25/03

25/03